



## Line Set Schedule

Last Revision - 03/25/2011

Line Set	From Plaster	Current Status
1	1' 7"	Main Valance
2	2' 3"	Main Drape
3	3' 8"	1st Electric
4	5' 0"	White Scrim
5	5' 8"	#1 Legs
6	6' 4"	Open
7	7' 0"	#1 Border
8	8' 4"	Screen (Front Projection Only) - SEE NOTE BELOW
9	9' 8"	2nd Electric
10	11' 8"	#2 Legs
11	13' 0"	#2 Border
12	13' 8"	Mid Stage Traveler
13	14' 4"	Open
14	15' 8"	3rd Electric
15	18' 4"	#3 Leg
16	19' 0"	Open
17	19' 8"	Open
18	20' 4"	Projection Screen - SEE NOTE BELOW
19	21' 0"	#3 Border
20	21' 8"	Open
21	23' 0"	4th Electric
22	24' 4"	#4 Leg
23	25' 8"	Open
24	27' 0"	Open
25	27' 4"	Sky Blue Cyclorama
26	28' 8"	Rear Traveler

The screens on Line Sets 8 and 18 are large and very heavy. If a production needs these line sets you must inform us at least two weeks in advance. There will be a charge of \$500 to remove a screen and a charge of \$500 to put the screen back in place. Screens can only be stored against the back wall of the stage due to their size and weight.

Higley Center for the Performing Arts, 4132 E. Pecos Rd., Gilbert, AZ 85295  
 Technical Director - Robert Zucker (480-279-7193) robert.zucker@husd.org